# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

## DRAFT TENDER SCHEDULE

**Issued to :**

**Original / Duplicate**
**Item No.**

**Name of the Work : Construction of Ward Office Building in Ward No. 10, Vidyaranyapura Sub Division. (Phase - 3).**

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 24.00 | Providing and laying in position plain cement concrete of **mix M7.5 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work. | Cum | 4211.38 | |
| 2 | 19.20 | Providing and laying in position plain cement concrete of **mix M20 with OPC cement @ 300 kgs, with 20mm** and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work. | Cum | 5224.74 | |
| 3 | 152.88 | Providing and fixing Special make glazed Vitrified tiles (Granomite finish) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 1456.44 | |
| 3.1 | 152.88 | **For First Floor** | | 1458.03 | |
| 4 | 87.26 | Flooring with 25mm to 40mm thick polished **tandur blue stone slabs** using mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 1017.60 | |
| 4.1 | 87.26 | **For First Floor** | | 1019.19 | |
| 5 | 1455.30 | Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S. flats and square rods as per approved design, drawning including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery etc complete as per specifications and directions of engineer in charge of the work. | Kgs | 95.40 | |
| 5.1 | 1245.51 | **For First Floor** | | 95.40 | |

| Sl. No. | Quantity. | Description | Unit | Rates | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 6 | 42.55 | Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of **class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure** including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work. | Cum | 5789.72 | |
| 7 | 203.50 | Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work. | Sqm | 187.62 | |

Signture of the Contractor

**Executive Engineer**
**Byatarayanapura Division**
**BBMP, Bangalore - 92**

ಶಿದ್ದವಡಿ ಮಾಡಿದಂತೆ
ಶಿದ್ದವಡಿ ಇಲ್ಲದ ಅಯವ್ಯಯವನ್ನು ನೀಡಲಾಗಿದೆ.
ಶಿದ್ದವಡಿಗಳ ಸಂಖ್ಯೆ .....NIL.....

Superintending Engineer
Yelahanka Zone
BBMP, Bangalore-92

31/10/2013